

ADDENDUM NUMBER 2

DATE: APRIL 29, 2025

PROJECT NAME: GRANITEVILLE ARMORY – KITCHEN UPFIT

OWNER'S PROJECT NUMBER: E24-9848-CB

ARCHITECT: GMK ASSOCIATES

TO: PROSPECTIVE BIDDERS

This addendum modifies the drawings and specifications for the above referenced project dated JANUARY 15 2025. Changes noted herein will become part of the contract.

Acknowledge receipt of this addendum in the space provided in the bid form. Failure to do so may disqualify the bidder.

This addendum consists of **3 page**.

PROJECT MANUAL:

1. Specification **09 7800 INTERIOR WALL PANEL**, insert the following specification in its entirety (see attached).
2. Specification **12 3100 MANUFACTURED METAL CASEWORK**, section **2.01 Manufacturers, A. Metal Casework**: add the following additional manufacturers:
 4. Uline; www.uline.com.
 5. Specialty Stainless; www.specialtystainless.com
 6. Webstaurant store; www.webstaurantstore.com

END OF ADDENDUM NUMBER 2

**SECTION 097800
INTERIOR WALL PANELING**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Metal interior wall paneling.

1.02 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Submit manufacturer's descriptive literature for each specified product. Include anchorage devices specific to project substrate types.
- C. Manufacturer's Instructions: Provide manufacturer's installation instructions.
- D. Maintenance Data: Include recommended instructions, methods, and materials for cleaning aluminum.
- E. Warranty Documentation: Manufacturer warranty; ensure that forms have been completed in Owner's name and registered with manufacturer.

1.03 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to project site in manufacturer's original packaging, marked with manufacturer's product identification.
- B. Store panels flat, indoors, on a clean, dry surface. Remove packaging and allow panels to acclimate to room temperature for 48 hours prior to installation.

1.04 WARRANTY

- A. See Section 017800 - Closeout Submittals for additional warranty requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Stainless Steel Metal Interior Wall Pane:
 - 1. MDC Interior Solutions; Architectural Metals: www.mdcwall.com/#sle.
 - 2. Hood Mart: <https://www.hoodmart.com>.
 - 3. Webstraunt Store: www.webstaurantstore.com

2.02 METAL INTERIOR WALL PANELING

- A. Metal Wall Panel System:
 - 1. Applications: As indicated on drawings.
 - 2. Panel Size: 4 by 8 feet.
 - 3. Thickness: 0.035 inch (20 guage).
 - 4. Finish: #4 finish.
 - 5. Substrate: As indicated on drawings.
- B. Materials: T-304 Stainless steel sheet..
- C. Fabrication: Shop fabricate to greatest extent possible.
- D. Adhesive: Type recommended by panel manufacturer.
- E. Accessories: Vertical channels between seams and caps at vertical and horizontal edges.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions and substrate flatness before starting work.
- B. Verify that substrate surfaces for adhered items are clean and smooth.
 - 1. Test painted or wall covering surfaces for adhesion in inconspicuous area, as recommended by manufacturer.

2. Comply with adhesive manufacturer's recommendations for remedial measures at locations and application conditions where adhesion test results are unsatisfactory.
- C. Start of installation constitutes acceptance of project conditions.

3.02 INSTALLATION

- A. Install panels in accordance with manufacturer's instructions.
- B. Cut and drill holes in panels with carbide tipped saw blades, drill bits, or snips.
- C. Apply adhesive to back side of panel using trowel recommended by adhesive manufacturer.
- D. Apply panels to wall with vertical joints plumb and horizontal joints level and pattern aligned with adjoining panels.
- E. Using a roller, apply pressure to panel face to ensure proper adhesion between surfaces.
- F. Install panels with manufacturer's recommended gaps for panel field and corner joints.
- G. Fill channels in trim with sealant before mounting to panel.
- H. Install trim with adhesive.
- I. Seal joints at wall base and between panels with approved sealant to prevent moisture intrusion.
- J. Remove excess sealant after paneling is installed and prior to curing.

3.03 CLEANING

- A. See Section 017000 - Execution and Closeout Requirements for additional requirements.
- B. Remove nonpermanent labels immediately after glazing installation is complete.
- C. Clean panel faces using cleaning agents and methods recommended by manufacturer to remove soiling.

3.04 CLOSEOUT ACTIVITIES

- A. See Section 017800 - Closeout Submittals for closeout submittals.

3.05 PROTECTION

- A. Protect installed interior wall paneling from subsequent construction operations.

END OF SECTION